

Footing Cost Comparison

Typical Footing Size: 2' x 2' x 10" w/ 2-#4 each way

Versus

16" x 16" x ½" Insta-Footing

Expense	Concrete footing	Insta-footing
Concrete cost 6-80# bags	\$26	0
Rebar (2-#4 each way)	\$7	0
Post Connector	\$6	included
Insta-footing cost	0	\$95
Labor to install*	2 hours	10 min.
Cost of labor @\$65/hr	\$130	\$11
Cure time	24 hours min.	0
Total Install Cost	\$169	\$106
Total time to install & cure	26 hours	10 min.
Cost savings w/Insta-footing	\$63 Savings per footing	
Time & Labor Savings	~26 hours	

*labor to install concrete is assuming cutting slab, digging out earth, setting rebar, mixing concrete, etc.